County of Henrico
Department of Public Works

Citizen's Information Meeting

Bethlehem Road Improvements

Project Location

North Arrow & Scale

N

1:40

Legend

- Proposed Road and Shared Use Path
- Proposed Stamped Concrete
- Proposed Sidewalk
- Grass Median
- Proposed Bike Lane
- Proposed Driveway (Modification to Existing Driveway)
- Proposed Driveway (Modification to Existing Driveway, Match In-Kind)
- Existing Right of Way
- Proposed Right of Way Line
- Proposed Permanent Drainage Easement
- Proposed Temp Construction Easement
- Proposed Improvements by Others

STORMWATER CONSIDERATIONS:
QUANTITY: SATISFIED BY THE TN RULE
QUALITY: SATISFIED BY PURCHASING NUTRIENT CREDITS

Bethlehem Road Improvements
Henrico County, Virginia

UPC 113260
State Project Number: 9999-043-R36

These plans are preliminary and unapproved and are not to be used for any type of construction or acquisition of rights-of-way. Additional easements for utility relocations, construction and permanent may be required beyond the proposed right-of-way shown on these plans.

Imagery Courtesy of Virginia Geographic Information Network (VGIN)

Additional survey being collected east of Lacy Lane.
BETHLEHEM ROAD
BEACON LN.
LIBBIE AVE.
SPENCER RD.
LACY LN.
US STAPLES MILL RD.
Proposed Improvements to be constructed by others
Proposed 6' Asphalt Shared Use Path
Proposed 6' Asphalt Bike Lane Overlay
Proposed Improvements to Existing Driveway
Proposed Temporary Construction Easement (Approximately 1,000 SF)
Proposed Temporary Construction Easement (Approximately 1,000 SF)
Proposed Temporary Construction Easement (Approximately 1,000 SF)